



STATE OF IDAHO  
DEPARTMENT OF  
ENVIRONMENTAL QUALITY

1410 North Hilton • Boise, Idaho 83706 • (208) 373-0502

Dirk Kempthorne, Governor  
Toni Hardesty, Director

October 28, 2005

**Certified Mail No. 7004 1160 0005 8739 4939**

Gale Lim  
Gale Lim Construction  
921 West 250 South  
Blackfoot, Idaho 83221

RE: Facility ID No. 777-00359, Gale Lim Construction, Portable  
Permit to Construct No. P-050316

Dear Mr. Lim:

The Idaho Department of Environmental Quality (DEQ) is issuing Permit to Construct (PTC) Number P-050316 for Gale Lim Construction, in accordance with IDAPA 58.01.01.200 through 228 (Rules for the Control of Air Pollution in Idaho).

This permit is based on your permit application received on May 18, 2005. This permit is effective immediately. This permit does not release Gale Lim Construction from compliance with all other applicable federal, state, or local laws, regulations, permits, or ordinances.

A representative of the Pocatello Regional office will contact you regarding a meeting with DEQ to discuss the permit terms and requirements. DEQ recommends the following representatives attend the meeting: your facility's plant manager, responsible official, environmental contact, and any operations staff responsible for day-to-day compliance with permit conditions.

Pursuant to IDAPA 58.01.23, you, as well as any other entity, may have the right to appeal this final agency action within 35 days of the date of this decision. However, prior to filing a petition for a contested case, I encourage you to call Dan Pitman at (208) 373-0502 to address any questions or concerns you may have with the enclosed permit.

Sincerely,

Martin Bauer, Administrator  
Air Quality Division

MB/DP/sd  
Enclosures

Permit No. P-050316



**Air Quality  
PERMIT TO CONSTRUCT**  
**State of Idaho**  
**Department of Environmental Quality**

**PERMIT No.:** P-050316

**FACILITY ID No.:** 777-00359

**AQCR:** Portable

**CLASS:** SM

**SIC:** 2951

**ZONE:** Portable

**UTM COORDINATE (km):** Portable

**1. PERMITTEE**

Gale Lim Construction

**2. PROJECT**

Gencor Hot-Mix Asphalt Plant

**3. MAILING ADDRESS**

921 West 250 South

**CITY**

Blackfoot

**STATE**

Idaho

**ZIP**

83221

**4. FACILITY CONTACT**

Gale Lim

**TITLE**

Owner

**TELEPHONE**

(208) 684-9299

**5. RESPONSIBLE OFFICIAL**

Gale Lim

**TITLE**

Owner

**TELEPHONE**

(208) 684-9299

**6. EXACT PLANT LOCATION**

Portable

**COUNTY**

Portable

**7. GENERAL NATURE OF BUSINESS & KINDS OF PRODUCTS**

Production of hot-mix asphalt

**8. GENERAL CONDITIONS**

This permit is issued according to IDAPA 58.01.01.200, *Rules for the Control of Air Pollution in Idaho*, and pertains only to emissions of air contaminants regulated by the state of Idaho and to the sources specifically allowed to be constructed or modified by this permit.

This permit (a) does not affect the title of the premises upon which the equipment is to be located; (b) does not release the permittee from any liability for any loss due to damage to person or property caused by, resulting from, or arising out of the design, installation, maintenance, or operation of the proposed equipment; (c) does not release the permittee from compliance with other applicable federal, state, tribal, or local laws, regulations, or ordinances; (d) in no manner implies or suggests that the Department of Environmental Quality (DEQ) or its officers, agents, or employees, assume any liability, directly or indirectly, for any loss due to damage to person or property caused by, resulting from, or arising out of design, installation, maintenance, or operation of the proposed equipment.

This permit will expire if construction has not begun within two years of its issue date or if construction is suspended for one year.

This permit has been granted on the basis of design information presented with its application. Changes of design or equipment may require DEQ approval pursuant to the *Rules for the Control of Air Pollution in Idaho*, IDAPA 58.01.01.200, et seq.

  
\_\_\_\_\_  
**TONI HARDESTY, DIRECTOR**  
**DEPARTMENT OF ENVIRONMENTAL QUALITY**

**DATE ISSUED:** October 28, 2005

## Table of Contents

ACRONYMS, UNITS, AND CHEMICAL NOMENCLATURE.....	3
1. PERMIT TO CONSTRUCT SCOPE.....	4
2. HOT-MIX ASPHALT PLANT.....	5
3. STATEWIDE REQUIREMENTS .....	6
4. OPERATIONS IN PM <sub>10</sub> NONATTAINMENT AREAS .....	12
5. PERMIT TO CONSTRUCT GENERAL PROVISIONS .....	13

## **Acronyms, Units, and Chemical Nomenclature**

CO	carbon monoxide
DEQ	Idaho Department of Environmental Quality
gr/dscf	grain per dry standard cubic foot
HMA	hot-mix asphalt
IDAPA	a numbering designation for all administrative rules in Idaho promulgated in accordance with the Idaho Administrative Procedures Act
km	kilometer
lb/hr	pound per hour
O&M	operations and maintenance
PM	particulate matter
PM <sub>10</sub>	particulate matter with an aerodynamic diameter less than or equal to a nominal 10 micrometers
ppm	parts per million
PTC	permit to construct
SIC	Standard Industrial Classification
T/hr	tons per hour
T/yr	tons per any consecutive 12-month period
UTM	Universal Transverse Mercator

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500-050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**1. PERMIT TO CONSTRUCT SCOPE**

**Purpose**

- This permit to construct (PTC) is for the operation of a new hot-mix asphalt plant.

**Regulated Sources**

- Table 1.1 lists all sources of emissions that are regulated in this PTC.

**Table 1.1 REGULATED EMISSIONS SOURCES**

<b>Permit Sections</b>	<b>Source Description</b>			<b>Emissions Control(s)</b>
2. Hot-mix Asphalt Plant	Manufacturer: Gencor, HS300 Type of HMA plant: Drum mix	Max. hot-mix asphalt production rate:300 T/hr HMA burner permitted fuel types: Natural gas, propane, ASTM Grade 2 fuel oil, and used oil	Drum dryer maximum rated heat input capacity: 88 MMBtu/hr	Baghouse: Manufacturer: PT 684-10
1. Generator Engine	Manufacturer: Caterpillar, 3412	Fuel: #2 Fuel oil	Fuel Consumption: 41 Gal/hr	None

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: ~~P-050500~~ 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**2. HOT-MIX ASPHALT PLANT**

**2.1 Process Description**

Stockpiled aggregate is transferred to feed bins. Aggregate is dispensed from the bins onto feeder conveyors, which transfer the aggregate to the drum mix dryer. Aggregate travels through the rotating drum dryer, aggregate may consist of up to 50% recycled asphalt. When dried, the aggregate is mixed with liquid asphalt cement. The resulting hot-mix asphalt (HMA) is then conveyed to hot storage bins until it can be loaded into trucks for transport off site or transferred to silos for temporary storage.

**2.2 Emissions Control Description**

Particulate matter (PM) emissions from the hot-mix asphalt drum dryer are controlled by a baghouse.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500-050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**3. STATEWIDE REQUIREMENTS**

The permittee shall comply with the following conditions when the portable hot-mix asphalt plant is operated anywhere (nonattainment, attainment, or unclassifiable areas) within the state of Idaho.

**Emissions Limits**

**3.1 Opacity Limit (NSPS)**

Visible emissions from the hot-mix asphalt facility shall not exhibit 20% opacity, or greater in accordance with 40 CFR 60.92(a)(2). Opacity shall be determined using EPA method 9.

**3.2 Opacity Limit (IDAPA)**

Emissions from any stack, vent, or other functionally equivalent opening shall not exceed 20% opacity for a period or periods aggregating more than three minutes in any 60-minutes in accordance with IDAPA 58.01.01.625. Opacity shall be determined using the procedures contained in IDAPA 58.01.01.625.

**3.3 Asphalt Dryer PM Grain Loading Emissions Limit**

Particulate matter (PM) emissions from the hot-mix asphalt stack shall not exceed 0.04 grains per dry standard cubic foot (gr/dscf) in accordance with 40 CFR Part 60.92(a)(1).

**3.4 Criteria Pollutant Emissions Limits**

The PM and PM<sub>10</sub> emissions from the hot-mix asphalt plant stack shall not exceed any corresponding emissions rate limits listed in Table 3.1.

**Table 3.1 ASPHALT PLANT STACK EMISSIONS LIMITS**

Source Description	PM		PM <sub>10</sub>	
	lb/hr <sup>a</sup>	T/yr <sup>b</sup>	lb/hr <sup>a</sup>	T/yr <sup>b</sup>
Asphalt Plant Stack	9.9	0.66	6.9	0.46

<sup>a</sup> pounds per hour  
<sup>b</sup> tons per consecutive 12-month period

**3.5 Toxic Air Pollutant Emissions Limit**

- Nickel emissions shall not exceed 2.5 pounds per year from the asphalt plant.
- Formaldehyde emissions shall not exceed 125 lbs per year from the asphalt plant and generator engine combined.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500 050310**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**3.6 Visible Fugitive Emission Limits at Property Boundary**

Visible fugitive dust emissions shall not be observed leaving the property boundary for a period or periods aggregating more than three minutes in any 60 minute period. Visible emissions shall be determined by Method 22, which is contained in 40 CFR Part 60 Appendix A, or by a DEQ-approved alternative method.

***Operating Requirements***

**3.7 Reasonable Control of Fugitive Emissions**

All reasonable precautions shall be taken to prevent particulate matter (PM) from becoming airborne in accordance with IDAPA 58.01.01.650-651. In determining what is reasonable, considerations will be given to factors such as the proximity of dust-emitting operations to human habitations and/or activities and atmospheric conditions that might affect the movement of PM. Some of the reasonable precautions include, but are not limited to, the following:

- Use, where practical, of water or chemicals for control of dust in the demolition of existing buildings or structures, construction operations, the grading of roads, or the clearing of lands.
- Application, where practical, of asphalt, oil, water, or suitable chemicals to, or covering of, dirt roads, material stockpiles, and other surfaces which can create dust.
- Installation and use, where practical, of hoods, fans, and fabric filters or equivalent systems to enclose and vent the handling of dusty materials. Adequate containment methods should be employed during sandblasting or other operations.
- Covering, where practical, of open-bodied trucks transporting materials likely to give rise to airborne dusts.
- Paving of roadways and their maintenance in a clean condition, where practical.
- Prompt removal of earth or other stored material from streets, where practical.

**3.8 Dryer Burner Fuel**

The fuel used in the hot-mix asphalt drum dryer shall be natural gas, propane, ASTM Grade 2 fuel oil or used oil.

**3.9 Used Oil Fuel Specifications**

In accordance with 40 CFR 279.11, with the exception of total halogens which are limited to 1,000 ppm, used oil burned for energy recovery shall not exceed any of the allowable levels listed in Table 3.2.



**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-~~050500~~ 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**Table 3.2 USED OIL SPECIFICATIONS<sup>1</sup>**

Constituent/property	Allowable level
Arsenic	5 ppm <sup>2</sup> maximum
Cadmium	2 ppm maximum
Chromium	10 ppm maximum
Lead	100 ppm maximum
Flash point	100 deg. F minimum
Total halogens	1,000 ppm maximum

<sup>1</sup> The specification does not apply to mixtures of used oil and hazardous waste that continue to be regulated as hazardous waste (see 40 CFR 279.10(b)).

<sup>2</sup> parts per million

**3.10 Fuel Oil and Used Oil Sulfur Content Limit**

- No ASTM Grade 2 fuel oil containing sulfur in excess of 0.5% by weight shall be burned in the hot-mix asphalt drum dryer.
- No used oil fuel containing sulfur in excess of 0.5% by weight shall be burned in the hot-mix asphalt drum dryer.

**3.11 Hot-Mix Asphalt Production Limits**

- The production rate of the hot-mix asphalt plant shall not exceed a maximum of 7,200 tons per day.
- The production rate of the hot-mix asphalt plant shall not exceed a maximum of 40,000 tons of hot-mix asphalt per any consecutive 12-month period.
- The hot-mix asphalt plant shall not use more than 3,600 tons of recycled asphalt per day.

**3.12 Baghouse Monitoring Equipment**

The permittee shall, in accordance with manufacturer specifications, install, calibrate, maintain, and operate equipment to continuously measure the pressure differential across the hot-mix asphalt drum dryer baghouse.

**3.13 Operations and Maintenance Manual**

Within 60 days of permit issuance the permittee shall have developed an O&M manual for the baghouse which controls the PM emissions from the hot-mix asphalt drum dryer. The O&M manual shall describe the procedures that will be followed to comply with General Provision 2 and the manufacturer specifications for the baghouse. The manual shall contain, at a minimum, the pressure drop range for the baghouse. The manual shall remain on site at all times and shall be made available to DEQ representatives upon request.

**3.14 Pressure Drop Across the Baghouse**

The pressure drop across the baghouse shall be maintained within manufacturer and O&M manual specifications. Documentation of both the manufacturer and O&M manual operating pressure drop specifications shall remain on site at all times and shall be made available to DEQ representatives upon request.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-~~050300~~ 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**3.15 Collocation**

The hot-mix asphalt plant shall not collocate with any other hot-mix asphalt plant.

***Monitoring and Recordkeeping Requirements***

**3.16 Operating Parameters**

The following parameters shall be monitored and recorded. Records of this information shall remain on site for the most recent two-year period and shall be made available to DEQ representatives upon request.

- Pressure drop across the baghouse once weekly when the drum dryer is operating
- Hot-mix asphalt production in tons per day, tons per month and tons per any consecutive 12 month period (tons per year)
- Tons of recycled asphalt used per day

**3.17 Reasonable Control Measures**

The permittee shall conduct a monthly facility-wide inspection of potential sources of fugitive emissions during daylight hours and under normal operating conditions to ensure that the methods used to reasonably control fugitive emissions are effective. If fugitive emissions are not being reasonably controlled, the permittee shall take corrective action as expeditiously as practicable. The permittee shall maintain records of the results of each fugitive emissions inspection. The records shall include, at a minimum, the date of each fugitive emissions inspection and a description of the following: the permittee's assessment of the conditions existing at the time fugitive emissions were present (if observed), any corrective action taken in response to the fugitive emissions, and the date the corrective action was taken. The monthly inspection is not required when the facility is not in operation.

Records of each facility-wide fugitive emissions inspection shall remain on site for the most recent two-year period and shall be made available to DEQ representatives upon request.

**3.18 Visible Emissions Monitoring**

The permittee shall conduct an inspection of visible emissions from the hot-mix asphalt drum dryer baghouse stack during daylight hours and under normal operating conditions once during each calendar month that the asphalt plant operates. The inspection shall consist of a see/no see evaluation of visible emissions. If any visible emissions are present from the hot-mix asphalt drum dryer baghouse stack, the permittee shall either take appropriate corrective action as expeditiously as practicable, or perform a Method 9 opacity test in accordance with the procedures outlined in IDAPA 58.01.01.625. A minimum of 30 observations shall be recorded when conducting the opacity test. If opacity is greater than 20% for a period or periods aggregating more than three minutes in any 60-minute period, the permittee shall take all necessary corrective action and report the exceedance in accordance with IDAPA 58.01.01.130-136.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

The permittee shall maintain records of the results of each visible emissions inspection and each opacity test when conducted. The records shall include, at a minimum, the date and results of each inspection and test and a description of the following: the permittee's assessment of the conditions existing at the time visible emissions are present (if observed), any corrective action taken in response to the visible emissions, and the date corrective action was taken. The monthly visible emissions inspection is not required when the facility is not in operation.

Records of each visible emissions inspection shall remain on site for the most recent two-year period and shall be made available to DEQ representatives upon request.

**3.19 Performance Testing Requirements**

3.19.1 Within 60 days after achieving the maximum production rate at which the affected facility will operate but not later than 180 days after initial start up of the source, a performance test shall be conducted on the hot-mix asphalt plant under worst-case normal operating conditions in accordance with IDAPA 58.01.01.157, General Provision 6 of this permit, and in accordance with 40 CFR 60.90 if the initial source test has not been conducted in accordance with that regulation. The performance test shall be conducted to demonstrate compliance with the applicable PM standards defined in 40 CFR 60.92 and the pound per hour PM emissions standard of Section 3.4 of this permit. The following shall be monitored and recorded during the performance tests:

- The hourly production rate of the hot-mix asphalt plant expressed as tons per hour
- The pressure drop across the baghouse
- The visible emissions observed during the performance tests

3.19.2 The permittee shall conduct performance tests at a frequency of no less than once every five years to demonstrate compliance with the 0.04 grains of PM per dry standard cubic foot (gr/dscf) emissions limit, the pound per hour PM emissions limit of Section 3.4 of this permit and the 20% opacity emissions limit of Section 3.2 of this permit.

**3.20 Used Oil Fuel Certification**

The permittee shall demonstrate compliance with the used oil fuel specifications in Permit Condition 3.9 by obtaining a used oil fuel certification from the used oil fuel supplier on an as-received basis or by having the fuel analyzed by a qualified laboratory. The certification shall include the following information:

- The name and address of the used oil supplier
- The measured concentration, expressed as ppm, of each constituent listed in Table 3.2
- The flash point of the used oil expressed as degrees Fahrenheit
- The analytical method or methods used to determine the concentration of each constituent and property (flash point) listed in Table 3.2
- The date and location of each sample
- The date of each certification analysis

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-~~050500~~ 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

Records of each certification shall remain on site for the most recent two-year period and shall be made available to DEQ representatives upon request.

**3.21 Sulfur Content Monitoring**

The permittee shall maintain purchase records or equivalent from the supplier that show the sulfur content of the fuel oil and used oil delivered to the facility on an as-received basis. Records of this information shall remain on site for the most recent two-year period and shall be made available to DEQ representatives upon request.

***Reporting Requirements***

**3.22 Performance Test Protocol**

At least 30 days prior to conducting any emission test, the permittee is encouraged to submit a written performance test protocol to DEQ in accordance with IDAPA 58.01.01.157.01.a.

**3.23 Performance Test Report**

In accordance with IDAPA 58.01.01.157.04, the permittee shall submit a written report of the performance test results to DEQ within 30 days of completion of the test.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-~~050500~~ 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**4. OPERATIONS IN PM<sub>10</sub> NONATTAINMENT AREAS**

The permittee shall comply with the following conditions when the portable hot-mix asphalt plant is operated in PM<sub>10</sub> nonattainment Areas.

- 4.1 The production rate of the hot-mix asphalt plant shall not exceed a maximum of 2,160 tons of hot-mix asphalt per day.
- 4.2 The hot-mix asphalt plant shall not use more than 1,080 tons of recycled asphalt per day.
- 4.3 The facility shall not operate in the Sandpoint PM<sub>10</sub> nonattainment area.
- 4.4 The permittee shall monitor and report in accordance with Sections 3.16 through 3.23 of this permit.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500-050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

**5. PERMIT TO CONSTRUCT GENERAL PROVISIONS**

1. The permittee has a continuing duty to comply with all terms and conditions of this permit. All emissions authorized herein shall be consistent with the terms and conditions of this permit and the *Rules for the Control of Air Pollution in Idaho*. The emissions of any pollutant in excess of the limitations specified herein, or noncompliance with any other condition or limitation contained in this permit, shall constitute a violation of this permit and the *Rules for the Control of Air Pollution in Idaho*, and the Environmental Protection and Health Act, Idaho Code §39-101, et seq.
2. The permittee shall at all times (except as provided in the *Rules for the Control of Air Pollution in Idaho*) maintain in good working order and operate as efficiently as practicable, all treatment or control facilities or systems installed or used to achieve compliance with the terms and conditions of this permit and other applicable Idaho laws for the control of air pollution.
3. The permittee shall allow the director, and/or the authorized representative(s), upon the presentation of credentials:
  - To enter, at reasonable times, upon the premises where an emissions source is located, or in which any records are required to be kept under the terms and conditions of this permit.
  - At reasonable times, to have access to and copy any records required to be kept under the terms and conditions of this permit, to inspect any monitoring methods required in this permit, and require stack compliance testing in conformance with IDAPA 58.01.01.157 when deemed appropriate by the director.
4. Nothing in this permit is intended to relieve or exempt the permittee from compliance with any applicable federal, state, or local law or regulation, except as specifically provided herein.
5. The permittee shall notify DEQ, in writing, of the required information for the following events within 5 working days after occurrence:
  - Initiation of Construction - Date
  - Completion/Cessation of Construction - Date
  - Actual Production Startup - Date
  - Initial Date of Achieving Maximum Production Rate - Production Rate and Date
6. If performance testing (air emissions source test) is required by this permit, the permittee shall provide notice of intent to test to DEQ at least 15 days prior to the scheduled test date or shorter time period as approved by DEQ. DEQ may, at its option, have an observer present at any emissions tests conducted on a source. DEQ requests that such testing not be performed on weekends or state holidays.

**AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-050500- 050316**

<b>Permittee:</b>	Gale Lim Construction	<b>Facility ID No.</b> 777-00359	<b>Date Issued:</b>	October 28, 2005
<b>Location:</b>	Portable			

All performance testing shall be conducted in accordance with the procedures in IDAPA 58.01.01.157. Without prior DEQ approval, any alternative testing is conducted solely at the permittee's risk. If the permittee fails to obtain prior written approval by DEQ for any testing deviations, DEQ may determine that the testing does not satisfy the testing requirements. Therefore, at least 30 days prior to conducting any performance test, the permittee is encouraged to submit a performance test protocol to DEQ for approval. The written protocol shall include a description of the test method(s) to be used, an explanation of any or unusual circumstances regarding the proposed test, and the proposed test schedule for conducting and reporting the test.

Within 30 days following the date in which a performance test required by this permit is concluded, the permittee shall submit to DEQ a performance test report. The written report shall include a description of the process, identification of the test method(s) used, equipment used, all process operating data collected during the test period, and test results, as well as raw test data and associated documentation, including any approved test protocol.

7. The provisions of this permit are severable, and if any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.
8. In accordance with IDAPA 58.01.01.123, all documents submitted to DEQ, including, but not limited to, records, monitoring data, supporting information, requests for confidential treatment, testing reports, or compliance certification shall contain a certification by a responsible official. The certification shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document(s) are true, accurate, and complete.