



STATE OF IDAHO  
DEPARTMENT OF  
ENVIRONMENTAL QUALITY

1118 F Street • Lewiston, Idaho 83501 • (208) 799-4370  
www.deq.idaho.gov

C.L. "Butch" Otter, Governor  
Curt Fransen, Director

May 12, 2015

Chris Wolffig  
USDA Forest Service  
104 Airport Rd.  
Grangeville, ID 83530

Subject: Water Quality Certification for NWW-2015-100-B03

Dear Mr. Wolffig,

Attached are the final §401 water quality certifications for the above referenced projects. The §401 process requires a public notice, and the comment period closed on May, 8 2015. No public comments regarding the §401 water quality certification were received by the Idaho Department of Environmental Quality. Therefore, DEQ is issuing the final certification.

If you have any questions or concerns, please do not hesitate to contact me at (208) 799-4370 or [Cynthia.Barrett@deq.idaho.gov](mailto:Cynthia.Barrett@deq.idaho.gov).

Sincerely,

A handwritten signature in black ink, appearing to read "Cynthia Barrett".

Cynthia Barrett  
Water Quality Manager  
Lewiston Regional Office

c: Eric Gerke, ACOE, Boise  
John Cardwell, TRIM Record  
Stephen Berry, TRIM Record



## Idaho Department of Environmental Quality Final §401 Water Quality Certification

May 12, 2015

**404 Permit Application Number:** NWW-2015-102-B03 Unnamed Tributary to Soda Creek Culvert Replacement

**Applicant/Authorized Agent:** USDA-Forest Service, Nez Perce-Clearwater National Forest

**Project Location:** T28North R10East S31 1/4NW 1/4NE

**Receiving Water Body:** Unnamed Tributary to Soda Creek

---

Pursuant to the provisions of Section 401(a)(1) of the Federal Water Pollution Control Act (Clean Water Act), as amended; 33 U.S.C. Section 1341(a)(1); and Idaho Code §§ 39-101 et seq. and 39-3601 et seq., the Idaho Department of Environmental Quality (DEQ) has authority to review activities receiving Section 404 dredge and fill permits and issue water quality certification decisions.

Based upon its review of the joint application for permit, received on March 31, 2015, DEQ certifies that if the permittee complies with the terms and conditions imposed by the permit along with the conditions set forth in this water quality certification, then there is reasonable assurance the activity will comply with the applicable requirements of Sections 301, 302, 303, 306, and 307 of the Clean Water Act, the Idaho Water Quality Standards (WQS) (IDAPA 58.01.02), and other appropriate water quality requirements of state law.

This certification does not constitute authorization of the permitted activities by any other state or federal agency or private person or entity. This certification does not excuse the permit holder from the obligation to obtain any other necessary approvals, authorizations, or permits.

### Project Description

The project will remove a 48-inch diameter corrugated metal pipe culvert and replace it with a 103-inch span by 71-inch rise by 74-foot long pipe arch bridge.

### Antidegradation Review

The WQS contain an antidegradation policy providing three levels of protection to water bodies in Idaho (IDAPA 58.01.02.051).

- Tier 1 Protection. The first level of protection applies to all water bodies subject to Clean Water Act jurisdiction and ensures that existing uses of a water body and the level of water quality necessary to protect those existing uses will be maintained and protected

(IDAPA 58.01.02.051.01; 58.01.02.052.01). Additionally, a Tier 1 review is performed for all new or reissued permits or licenses (IDAPA 58.01.02.052.07).

- Tier 2 Protection. The second level of protection applies to those water bodies considered high quality and ensures that no lowering of water quality will be allowed unless deemed necessary to accommodate important economic or social development (IDAPA 58.01.02.051.02; 58.01.02.052.08).
- Tier 3 Protection. The third level of protection applies to water bodies that have been designated outstanding resource waters and requires that activities not cause a lowering of water quality (IDAPA 58.01.02.051.03; 58.01.02.052.09).

DEQ is employing a water body by water body approach to implementing Idaho's antidegradation policy. This approach means that any water body fully supporting its beneficial uses will be considered high quality (IDAPA 58.01.02.052.05.a). Any water body not fully supporting its beneficial uses will be provided Tier 1 protection for that use, unless specific circumstances warranting Tier 2 protection are met (IDAPA 58.01.02.052.05.c). The most recent federally approved Integrated Report and supporting data are used to determine support status and the tier of protection (IDAPA 58.01.02.052.05).

### ***Pollutants of Concern***

The primary pollutant of concern for this project is sediment. As part of the Section 401 water quality certification, DEQ is requiring the applicant comply with various conditions to protect water quality and to meet Idaho WQS, including the water quality criteria applicable to sediment.

### ***Receiving Water Body Level of Protection***

This project is located on an unnamed tributary to Soda Creek within the South Fork Clearwater Subbasin assessment unit (AU) ID17060305CL046\_02 (Soda Creek - source to mouth). This AU has the following designated beneficial uses: cold water aquatic life, salmonid spawning, and secondary contact recreation. In addition to these uses, all waters of the state are protected for agricultural and industrial water supply, wildlife habitat, and aesthetics (IDAPA 58.01.02.100).

The cold water aquatic life and salmonid spawning uses in the unnamed tributary to Soda Creek are not fully supported due to excess temperature (*South Fork Clearwater TMDL March, 2004*). The secondary contact recreation beneficial use has not yet been assessed; however the applicant has agreed that this water body is high quality with respect to secondary contact recreation. As such DEQ will provide Tier 1 protection for the aquatic life use and salmonid spawning beneficial use and Tier 2 protection, in addition to Tier 1, for the recreation beneficial use (IDAPA 58.01.02.051.01; 58.01.02.051.02).

The only pollutant of concern associated with this project is sediment, but sediment is not relevant to recreational uses; therefore, it is unnecessary for DEQ to conduct a Tier 2 review for this AU because this project will not create impacts that could affect the recreation use.

### ***Protection and Maintenance of Existing Uses (Tier 1 Protection)***

As noted above, a Tier 1 review is performed for all new or reissued permits or licenses, applies to all waters subject to the jurisdiction of the Clean Water Act, and requires demonstration that existing uses and the level of water quality necessary to protect existing uses shall be maintained and protected. The numeric and narrative criteria in the WQS are set at levels that ensure protection of designated beneficial uses.

Water bodies not supporting existing or designated beneficial uses must be identified as water quality limited, and a total maximum daily load (TMDL) must be prepared for those pollutants causing impairment. This AU (ID17060305CL046\_02) is included in the *South Fork Clearwater Subbasin Assessment and TMDL (March 2004)*.

*The South Fork Clearwater River TMDL (March, 2004)* was developed to address impairments to multiple AUs within the subbasin. The TMDL determined that the Soda Creek AU is impaired for temperature exceedances. Heat energy is transferred directly from the sun to the stream by solar radiation. In order to improve stream temperature, restored riparian communities and stream channels are needed. Therefore, it is necessary to ensure that project activities do not cause further temperature exceedances, whether directly or indirectly. Project activities are not expected to contribute sources of temperature to the unnamed tributary to Soda Creek; no trees or canopy will be removed and banks will be reseeded after construction.

The pollutant of concern for this project is sediment. Sediment is not relevant to recreational uses, but it is relevant to aquatic life use. The project will replace one undersized culvert on the unnamed tributary to Soda Creek, stabilize and reshape 0.08 acres of open channel and place riprap at the inlet and outlet to prevent erosion after the new pipe arch bridge is installed. Soil disturbances will be limited to the construction area; water, soil, and erosion control best management practices (BMPs) will be in place during construction. A temporary coffer dam will be used to divert water around the project area during construction. The applicant will implement, install, maintain, monitor, and adaptively manage BMPs directed toward reducing erosion and minimizing turbidity levels in receiving water bodies downstream of the project. In addition, permanent erosion and sediment controls will be implemented that will minimize or prevent future sediment contributions from the project area.

As long as the project is conducted in accordance with the provisions of the project plans, Section 404 permit and conditions of this certification, then there is reasonable assurance the project will comply with the state's numeric and narrative criteria. These criteria are set at levels that protect and maintain designated and existing beneficial uses. In addition, the project will be consistent with the *South Fork Clearwater River Subbasin Assessment and TMDL (March, 2004)*.

There is no available information indicating the presence of any existing beneficial uses aside from those that are already presumed and discussed above; therefore, the permit ensures that the level of water quality necessary to protect both presumed and existing uses is maintained and protected in compliance with the Tier 1 provisions of Idaho's WQS (IDAPA 58.01.02.051.01 and 58.01.02.052.07).

## Conditions Necessary to Ensure Compliance with Water Quality Standards or Other Appropriate Water Quality Requirements of State Law

### **General Conditions**

1. This certification is conditioned upon the requirement that any modification (e.g., change in BMPs, work windows, etc.) of the permitted activity shall first be provided to DEQ for review to determine compliance with Idaho WQS and to provide additional certification pursuant to Section 401. Such modifications may not be implemented until DEQ has determined whether additional certification is necessary.
2. DEQ reserves the right to modify, amend, or revoke this certification if DEQ determines that, due to changes in relevant circumstances—including without limitation, changes in project activities, the characteristics of the receiving water bodies, or state WQS—there is no longer reasonable assurance of compliance with WQS or other appropriate requirements of state law.
3. If ownership of the project changes, the certification holder shall notify DEQ, in writing, upon transferring this ownership or responsibility for compliance with these conditions to another person or party. The new owner/operator shall request, in writing, the transfer of this water quality certification to his/her name.
4. A copy of this certification must be kept on the job site and readily available for review by any contractor working on the project and any federal, state, or local government personnel.
5. The applicant shall provide access to the project site and all mitigation sites upon request by DEQ personnel for site inspections, monitoring, and/or to ensure that conditions of this certification are being met.
6. The applicant is responsible for all work done by contractors and must ensure the contractors are informed of and follow all the conditions described in this certification and the Section 404 permit.
7. If this project disturbs more than 1 acre and there is potential for discharge of stormwater to waters of the state, coverage under the EPA Stormwater Construction General Permit *must* be obtained. More information can be found at <http://yosemite.epa.gov/R10/WATER.NSF/NPDES+Permits/Region+10+CGP+resources>.

### **Fill Material**

1. Fill material shall be free of organic and easily suspendable fine material. The fill material to be placed shall include clean earth fill, sand, and stone only.
2. Fill material shall not be placed in a location or in a manner that impairs surface or subsurface water flow into or out of any wetland area.
3. Placement of fill material in existing vegetated wetlands shall be minimized to the greatest extent possible.
4. All temporary fills shall be removed in their entirety on or before construction completion. Straw wattles, bales and sand bags will be removed from the diversion structure and disposed of in an upland off site location.

5. Excavated or staged fill material must be placed so it is isolated from the water edge or wetlands and not placed where it could re-enter waters of the state uncontrolled.

### **Erosion and Sediment Control**

1. BMPs for sediment and erosion control suitable to prevent exceedances of state WQS shall be selected and installed before starting construction at the site. One resource that may be used in evaluating appropriate BMPs is DEQ's *Catalog of Stormwater Best Management Practices for Idaho Cities and Counties*, available online at <http://www.deq.idaho.gov/media/494058-entire.pdf>. Other resources may also be used for selecting appropriate BMPs.
2. One of the first construction activities shall be placing permanent and/or temporary erosion and sediment control measures around the perimeter of the project or initial work areas to protect the project water resources.
3. Permanent erosion and sediment control measures shall be installed in a manner that will provide long-term sediment and erosion control to prevent excess sediment from entering waters of the state.
4. Top elevations of bank stabilization shall be such that adequate freeboard is provided to protect from erosion at 100-year design flood elevation.
5. Structural fill or bank protection shall consist of materials that are placed and maintained to withstand predictable high flows in the waters of the state.
6. A BMP inspection and maintenance plan must be developed and implemented. At a minimum, BMPs must be inspected and maintained daily during project implementation.
7. BMP effectiveness shall be monitored during project implementation. BMPs shall be replaced or augmented if they are not effective.
8. All construction debris shall be properly disposed of so it cannot enter waters of the state or cause water quality degradation.
9. Disturbed areas suitable for vegetation shall be seeded or revegetated to prevent subsequent soil erosion.
10. Maximum fill slopes shall be such that material is structurally stable once placed and does not slough into the stream channel during construction, during periods prior to revegetation, or after vegetation is established.
11. To the extent reasonable and cost-effective, the activity submitted for certification shall be designed to minimize subsequent maintenance.

### **Turbidity**

1. All practical BMPs on disturbed banks and within the waters of the state must be implemented to minimize turbidity. Visual observation is acceptable to determine whether BMPs are functioning properly. If a plume is observed, the project may be causing an exceedance of WQS and the permittee must inspect the condition of the projects BMPs. If the BMPs appear to be functioning to their fullest capability, then the permittee must modify the existing BMPs or implement additional BMPs.
2. Turbidity monitoring must be conducted each day during project implementation when project activities may result in turbidity increases above background levels. If the

downstream turbidity exceeds upstream turbidity by fifty (50) nephelometric turbidity units (NTU) or more, or more than twenty-five (25) NTU for more than ten (10) consecutive days, the project is causing an exceedance of the WQS. If an exceedance occurs, the permittee must inspect the condition of the project BMPs. If the BMPs appear to be functioning to their fullest capability, then the applicant must modify the BMPs or implement additional BMPs.

### ***In-water Work***

1. Work in open water is to be kept at a minimum and only when necessary. Equipment shall work from an upland site to minimize disturbance of waters of the state. If this is not practicable, appropriate measures must be taken to ensure disturbance to the waters of the state is minimized.
2. Construction affecting the bed or banks shall take place only during periods of low flow.
3. Fording of the channel is not permitted. Temporary bridges or other structures shall be built if crossings are necessary.
  - a. Temporary crossings must be perpendicular to channels and located in areas with the least impact. The temporary crossings must be supplemented with clean gravel or treated with other mitigation methods at least as effective in reducing impacts. Temporary crossings must be removed as soon as possible after the project is completed or the crossing is no longer needed.
4. Activities in spawning areas must be avoided to the maximum extent practicable.
5. Work in waters of the state shall be restricted to areas specified in the application.
6. To minimize sediment transport, stream channel or stream bank stabilization must be completed prior to returning water to a dewatered segment.

### ***Pollutants/Toxics***

1. The use of chemicals such as soil stabilizers, dust palliatives, sterilants, growth inhibitors, fertilizers, and deicing salts during construction and operation should be limited to the best estimate of optimum application rates. All reasonable measures shall be taken to avoid excess application and introduction of chemicals into waters of the state.

### ***Vegetation Protection and Restoration***

1. Disturbance of existing wetlands and native vegetation shall be kept to a minimum.
2. To the maximum extent practical, staging areas and access points should be placed in open, upland areas.
3. Fencing and other barriers should be used to mark the construction areas.
4. Where possible, alternative equipment should be used (e.g., spider hoe or crane).

### ***Management of Hazardous or Deleterious Materials***

1. Petroleum products and hazardous, toxic, and/or deleterious materials shall not be stored, disposed of, or accumulated adjacent to or in the immediate vicinity of waters of the state. Adequate measures and controls must be in place to ensure that those materials will

not enter waters of the state as a result of high water, precipitation runoff, wind, storage facility failure, accidents in operation, or unauthorized third-party activities.

2. Vegetable-based hydraulic fluid should be used on equipment operating in or directly adjacent to the channel if this fluid is available.
3. Daily inspections of all fluid systems on equipment to be used in or near waters of the state shall be done to ensure no leaks or potential leaks exist prior to equipment use. A log book of these inspections shall be kept on site and provided to DEQ upon request.
4. Equipment and machinery must be removed from the vicinity of the waters of the state prior to refueling, repair, and/or maintenance.
5. Emergency spill procedures shall be in place and may include a spill response kit (e.g., oil absorbent booms or other equipment).
6. In accordance with IDAPA 58.01.02.850, in the event of an unauthorized release of hazardous material to state waters or to land such that there is a likelihood that it will enter state waters, the responsible persons in charge must
  - b. Make every reasonable effort to abate and stop a continuing spill.
  - c. Make every reasonable effort to contain spilled material in such a manner that it will not reach surface or ground waters of the state.
  - d. Immediately notify DEQ of the spill by calling the Idaho State Communications Center at 1-800-632-8000.
  - e. Collect, remove, and dispose of the spilled material in a manner approved by DEQ.
7. In accordance with IDAPA 58.01.02.851.04, any aboveground spill or overflow of petroleum that results in a release that exceeds 25 gallons *or that causes a sheen on a nearby surface water* shall be reported to DEQ within 24 hours and corrective action in accordance with IDAPA 58.01.02.852 shall be taken.
8. Any release that causes a sheen (of any size) in waters of the state must be reported *immediately* to the National Response Center at 1-800-424-8802 and DEQ by calling the Idaho State Communications Center at 1-800-632-8000.

### **Culverts**

1. The culvert shall not constrict the stream channel and shall not be angled such that the outflow is directed toward the stream bank. The culvert's flow line shall match the existing stream invert at its entrance and exit. Adequate grade control shall be installed to prevent channel down cutting or excessive deposition from occurring.
2. The culvert shall be installed such that it does not impede fish passage.
3. The culvert outflow shall be armored with riprap to provide erosion control. This riprap will be clean, angular, dense rock that is free of fines and resistant to aquatic decomposition.
4. Culverts shall be sized appropriately to maintain the natural drainage patterns.

### **Right to Appeal Final Certification**

The final Section 401 Water Quality Certification may be appealed by submitting a petition to initiate a contested case, pursuant to Idaho Code § 39-107(5) and the "Rules of Administrative Procedure before the Board of Environmental Quality" (IDAPA 58.01.23), within 35 days of the date of the final certification.

Questions or comments regarding the actions taken in this certification should be directed to Mark Sellet Idaho DEQ Lewiston region at (208) 799-4370 or email at [mark.sellet@deq.idaho.gov](mailto:mark.sellet@deq.idaho.gov).



---

John Cardwell  
Regional Administrator  
Lewiston Regional Office